

Construction of groyne at Digha



Although the navigability condition of the Harbour basin and Inner channel of the Shankarpur Fishing Harbour has improved owing to dredging, the out fall at sea gets choked owing to formation of sand spit on the eastern side of the channel, thereby the purpose of dredging the inner channel got frustrated. This problem is addressed by construction of a groyne (Submerged Breakwater) on the eastern side along with straightening of the embayed channel by dredging at the sea mouth. The work is completed in April, 2005. The cost of the project is Rs. 640 lakh.

